



First Sprout

LA15

TUNTEX™

First Sprout

Inspired by the quiet renewal of an early spring garden, LA15 First Sprout sets the stage with seven understated shades, defining the essence of modern luxury. Designed for spaces that value minimalism and inner peace, it serves as a soft architectural retreat from the urban rush.





LA1501 Ashlar



LA1502 Ashlar



LA1505 Ashlar



LA1504 Ashlar



LA1501 Ashlar



LA1502 Ashlar







LA1503 Ashlar



LA1506 Ashlar



LA1504 Ashlar




LA1501
Cloud



LA1502
Warm Soil




LA1503
Fog



LA1504
Morning Haze



LA1505
Clear Sky



LA1506
Pale Green



LA1507
Fresh Green

Style	LA15 "First Sprout"
Construction	Multi Hi / Lo Loop
Pile Fibre	nexlon™ Premium Solution Dyed Nylon featured with aircell
Dye Method	Solution Dyed
Gauge	1/10 G
Pile Height	8.0-3.5 mm
Total Thickness	11.8 mm (±0.5 mm)
Tile size	500 mm × 1000 mm
Total Weight	Approx. 3350 g/m ²
Secondary Back	LUXCUSHION™
Stain Resistance	Stainshield Treatment: STAINSHIELD™
Soil Resistance	Soil Guard Treatment: SOILGUARD™
Odor Reducer	Ecofresh Treatment: ECOFRESH™
Anti-microbial	Microshield Treatment: MICROSHIELD™

Wear Warranty	Product is warranted not to lose more than 10% pile fibre by weight in normal commercial use within 15 years.
Colour Fastness	15 Year Warranty AATCC 16. Grade 4 - Little or no change.
Static Electricity	Permanent Lifetime Protection - less than 2.0 kV.
Dimensional Stability	Warranted not to change in size by more than 0.5 mm in normal use. Will not dome or dish in normal use.
Installation	Tackifier or Releasable adhesive Recommended.
Sustainability	All yarns used are Solution dyed to minimise use of water and exclude any effluent production. ISO 14001 and ISO 9001.

Health Product Declaration (HPD).

U.S. CRI Green Label Plus Certificate.

Singapore Green Building Council Product Certificate - 4 Ticks "Leader".

Passes ASTM Flammability Test.
Flammability: Passes (ASTM E648)
Smoke Density: Passes (ASTM E662)

Passes AATCC Static Propensity Test.
Static Propensity: ≤ 2.0 kV (AATCC 134)

Passes the Quality Test of China National Carpet Quality Test Center.

Passes the Flammability Test and Environmental Protection Test of the China National Fire and Construction Quality Surveillance Center.

ISO 9001 Quality Management System.

ISO 14001 Environmental Management System.

ISO 45001 Healthy & Safety Management System.



